

**ROGERS STATE UNIVERSITY
1701 W. WILL ROGES BLVD.
CLAREMORE, OK 74017**

RE: Addendum No. 1

PROJECT: Request for Bid – Library Roof Replacement – RFB 2425-17

DATE OF REQUEST FOR BID: March 30, 2025

DATE OF ADDENDUM ISSUE: April 25, 2025

THIS SCOPE OF WORK IS HEREBY MADE PART OF THE CONTRACT AS THOUGH IT HAD BEEN INCLUDED ORIGINALLY THEREIN, AND IT SHALL SUPERSEDE ANYTHING CONTAINED IN THE CONTRACT WITH WHICH IT MIGHT CONFLICT.

Change:

Item No, 1- Currently there are two clock tower roofs sections that were to the roofs replaced with TPO. The existing roof sections are metal capped. The lower section is in decent condition (see photos). The upper section is in poor condition. (see photos) Contractor is to clean the surface, apply rust prohibits and apply a silicone roof coating to seal both roof sections.

Additions:

Item No. 1 – The Contractor will remove and dispose of the architectural railings at both the east and west side, roof line. New railings will be done by others.

Clarifications:

Item No. 1 – Equipment curbs will not have to be extended in height.







END OF ADDENDUM